



Addendum # 3, issued Oct 18, 2023

Ref: ITT PCSP-PW-2023-02

School Road Storm Water & Resurfacing

Owner: Town of Portugal Cove-St. Philips

Project Name: PCSP-PW-2023-02, School Road Storm Water & Resurfacing

ITT Date Issued: October 16, 2023

1. This Amendment shall form an integral part of the specification to be read in conjunction therewith. This Amendment shall take precedence over all forms of the aforementioned specification with which it may prove to be at variance or may otherwise be qualified in writing by authorized personnel.

2. The General Conditions and all documents issued with this specification shall apply to govern all phases of the work covered by this Amendment.

3. The purpose of this Amendment is to inform bidders of clarifications to the contract documents.

To advise Contractors of the following clarifications:

1. Install rigid insulation below new 600 mm HDPE storm water pipe where pipe passes over existing watermain at approximately station 0+015. Insulation shall be 100 mm in total thickness, Styrofoam HI 40 or approved equal. Insulation shall be positioned to extend a minimum of 1,200 mm in each direction from the intersection point of the longitudinal axis of the two pipes. The insulation shall be placed horizontally on a prepared Class B granular base (150 mm thickness) and have minimum plan dimensions of 2,400 mm x 2,400 mm. All work associated with the insulation and granular base shall be considered incidental to and included in the Pay Item for the 600 mm HDPE storm water pipe. Reference Drawing C3.
2. Closing date has been changed from October 23, 2023 at 2:00 pm NDT to October 25, 2023 at 2:00pm NDT.
3. Public opening date has been changed from October 23, 2023 at 2:30 pm NDT to October 25, 2023 at 2:30pm NDT.

1119 Thorburn Road Portugal Cove-St. Philip's A1M 1T6 T: 895-8000 F: 895-3780 www.pcsp.ca